

### The presentation



- Field of application
- Background
- Best of two worlds
- Structure
- Some challenges
- Summary
















### Risk level in the Norwegian Petroleum Industry



- Yearly monitring of risk level
- Accidents, questionnaires, work related illnessess, special studies
- «The lowest» risk level in the industry




#### Lost Time Accidents





### **Key HSE Regulators**









### **HSE** Regulations












# Risk reduction principles

- As Low As Reasonably Practicable (ALARP)
- Best available technology (BAT)
- Prevention on work group level
- Precautionary
- Substitution
- (Cost Benefit)







# NORSUK Norsk konkurransefortrinn på norsk sokkel (Norwegian)

### (trans. Competitive and cost effective new building and modifications on the Norwegian Continental Shelf)

- S-002 rev. 1 1993 (Terje Salbo (Statoil), Urban Kjellen (Hydro))
- Last revision 2004 (rev. 4)
- Based on international standards and industry best practice







http://www.standard.no/en/sectors/energiog-klima/petroleum/



### NCKSOK S-002 Working Environment

#### 1 Scope

This NORSOK standard applies to the design of new installations and modification or upgrading of existing installations for offshore drilling, production, and utilisation and pipeline transportation of petroleum, including accommodation units for such activities.

This NORSOK standard stipulates design requirements related to the working environment of petroleum installations as well as requirements regarding systematic management of working environment issues in project development and the design process.

The purpose of this NORSOK standard is to ensure that the design of the installation promotes the quality of the working environment during the operational phase.




#### NORSOK S-002




- Human centered design process
- Extracts and presents core elements of 50-60 international WE standards
- It's free (<u>www.standard.no</u>), however, it makes these international standards mandatory for use in Norwegian Oil & Gas industry, which is not free ........













#### Prescriptive requirements

Area requiremets (WEAL)

#### Functional requirements

Personal exposure

5.5.2 Noise limits

zone shall be implemented.

NORSOK standard S-002 Rev. 4, August 2004

Room description	Level of manning *	Average illuminance level (lux)*	Temperature min/max *C	Vibration	Noise total dB(A)	Noise HVAC dB(A)
External walkways and access ways		100	Outdoor		90 '	
Stairs, wakways and access ways in work areas	n enclosed	150			60 - 80	
Lay down area		200			75 °	
Muster are a	U	200	Outdoor	2	75	
Fire pump room	U	200	5 - 35	3	110 **	80
Emergency generator room	U	200	5 - 35	3	110 **	
Unmanned machinery room	Ų	200	5 - 35	3	110 **	80
General process and utility area	1	200	Outdoor5 - 35	3	85/90*	
HVAC room	U	200	5 - 35	3	90	
Switchboard and transformer room	- 1	200	5 - 35	2	85	70
Central control room	М	500 Adjustable	20 - 24	1	46'	40
Local control room	- 1	400	19 - 26	2	60	50
Coffee bass outside LQ	М	150	19 - 26	2	60,	50
Battery room	U	200	5 - 35	3	85	70
Main generator room	U	200	5 - 35	3	85.90*	70
Inst/EL workshop	М	500	19 - 26	2	65 **	50
Mechanical workshop/welding	м	500	16 - 26	2	65**	50
Stores - Large parts		200	16 - 26	2	65	60
Stores - Small parts		300	16 - 26	2	65	60
Labor atory	UM	500	19 - 26	2	60	50
Paint shop	- 1	500	16 - 26	2	65	55
Sandblasting room	- 1	300	16 - 26	2	65 * 1	55
Wickshop office	м	500	19 - 26	2	55	50

5.5.2.0-2 The individual employee's maximum exposure to noise during a 12 h working day is 83 dB(A).

5.5.2.0-3 The maximum allowable noise level in any situation is 130 dB(C) ("peak"). This limit also applies to enclosed "normally unmanned areas".

5.5.2.0-4 Annex A deals with vibration limits and area noise level limits, total and for HVAC.

5.5.2.0-5 The area noise level limits shall apply as the maximum sound pressure level at any location within an area, but not closer than 1 m to equipment and other noisy installations.

5.5.2.0-6 All limits refer to broadband noise without any distinct tonal characteristics. In case of tonal characteristics, the noise level limit shall be set 5dB lower.

5.5.2.0-7 For areas where the area noise limit is 95 dB(A) or 90 dB(A), the limit of 90 dB(A) shall apply only where a lower limit is undeasible. If an area limit of 90 dB(A) is incompatible with the individual

employee's maximum noise exposure, technical measures to reduce the need to stay in the noise



### The core NORSOK S-002 process





Figure G. 1 - Processes to implement prescriptive and goal-oriented WE requirements

#### 4.4.7 Noise and vibration control

- 4.4.7.0-1 During project development, the procedure for noise control in Annex H, or a procedure documented to be of equivalent functionality and quality, shall be applied.
- 4.4.7.0-2 During concept definition and optimisation/FEED, the activity shall ensure that:
- 4.4.7.0-3 major noise and vibration sources are identified,
- 4.4.7.0-4 possible use of low-noise equipment is evaluated,
- 4.4.7.0-5 a review of the localisation of noisy equipment and noise-exposed areas in relation to quiet areas
  - is performed, and the use of "buffer" zones is evaluated,
- 4.4.7.0-6 area noise level limits (total and HVAC) are specified,
- 4.4.7.0-7 preliminary predictions of area noise levels and personnel exposure levels are performed.
- 4.4.7.0-8 noise data sheets are issued for high-noise equipment to be ordered in the FEED phase. The
   equipment noise level limits shall be based on the project's area limits, and shall take into account
   other noise sources that are planned in the area, and area/room characteristics.



# Working environment



Industry standard for modifications and new buildings of offshore installations

- WE program
  - Design basis (WEAL)
  - Activity list
  - Systematically follow-up of modification and new buildings
  - Worker involvement
- Required analyses
- Functional and descriptive requirements
- Knowledge requirements





Foreword				
Introduction				
1		Scope	3	
2	2.1 2.2	Normative and informative references Normative references Informative references	<b>3</b> 3 4	
3	3.1 3.2	<b>Terms, definitions and abbreviations</b> Terms and definitions Abbreviations	<b>5</b> 5 6	
4	4.1 4.2 4.3 4.4 4.5	Systematic management of working environment in design and fabrication General Management system Working environment (WE) design basis Working environment analyses Verification and validation of design	<b>7</b> 7 7 8 10 15	
5	5.1 5.2 5.3 5.4 5.5 5.6 5.7 5.8 5.9 5.10	Working environment requirements  Arrangements Ergonomics Technical appliances Chemical substances and products Noise and vibration Illumination Indoor climate Outdoor operations Electromagnetic fields Radioactive sources - Ionising radiation	16 16 17 20 20 21 24 25 26 26	
Annex A (normative) Working environment area limits				
Annex B (normative) Vertical and horizontal clearances and distances				
Annex C (normative) Detailed requirements related to installation areas				
Annex D (normative) Vibration limit curves				

Annex E (normative) Working environment area chart

Annex H (normative) Procedure for noise control

Annex G (informative) Examples of methods for analysis of the working environment

Annex F (informative) Noise data sheet





39

41

42


48

## WE requirements in NORSOK

- NORSOK C-001 Living quarters area
- NORSOK C-002 Architectural components and equipment
- NORSOK S-002 Working Environment
- NORSOK S-005 Machinery Safety
- + Other disciplinary standards




## NORSOK S-002 gives an example of Winnelyse preferable should be conducted in a normal rojectory.






# Trends in project executions

#### Sequential traditional long time planning and execution projects



#### Fast track multi sequential projects



Planning and execution of projects moves abroad (EU, America, Asia)



#### Some reflections



- "The Project" a new first time experience for the project organization – but not for the industry
- The analyses require a mature understanding of the manning, operation and task required to operate the platform / rig
- Area limits are difficult to implement in a design process
- The projects often fails in how they are addressing, implementing, and verifying that they are fulfilling the goal oriented requirements in the projects
- The required analysis is done retrospective to document compliance with both Ch 4 and Ch 5 requirements



# The rature NORSOK S-002 is under revision

- Outdated references and terminology
- Difficult to apply internationally
- "New" project models
- Some important requirements missing
- Overlaps with NORSOK S-005

Hopefully issued for comments Q2-3 2014



#### Summary



- NORSOK S-002 proven use full
- A balance between descriptive and functional requirements
- Human / work task centered process
- Involvement of the workers in the design process
- Future ?
  - Performance (emission) criteria's set for equipment
  - Stricter and simplified requirements
  - Analysis to prove compliance with functional requirements when not feasible to comply with the descriptive requirements





### proactima.com

Prepared.



## Systematically follow-up - The Working Environment Programme

- A WE programme shall be established for every project phase.
- The WE programme may be a separate document or integrated into the project's HSE programme, and shall be linked to the project execution plan.



- The WE programme shall
  - define the project's WE objectives
  - define risk acceptance criteria for occupational safety, human error and health risks
  - State references to applicable WE requirements and procedures
  - describe means of ensuring the statutory worker participation in the design process



- The WE programme shall include an activity plan stipulating the responsibilities, schedule and deliverables for the various activities to manage WE in the design process.
- In particular, the WE analyses shall be planned with due consideration of the needs for timely input to design and procurement, and needs for verification and documentation.
- The WE activity plan shall be maintained to provide status regarding execution and documentation of the various WE management activities.



- Deviations from WE requirements shall be subject to the project's nonconformity procedures.
- A follow-up system shall be established that enables proper documentation, handling, follow-up and closeout of agreed actions and recommendations from the various WE studies and analysis in the project. The WE follow-up system shall be integrated in the overall HSE management system in the project.



- To document status regarding implementation of WE requirements, Working Environment Area Charts (WEAC's) shall be issued at predefined project milestones
- In principle, a WEAC shall be prepared for each room and area on the installation.



# Working Environment Activity Plan (example)

- This Working Environment Activity Plan (WE Activity Plan) provides information on WE activities and documentation to be performed or issued by xxx during execution of xxx EPCH Project.
- This activity plan supports project /1/ Working Environment Program, doc. no. xxx and is established for survey and status reporting between Company and Contractor throughout Project



# Working Environment Activity Plan (example)

- The plan contains planning and status information provided in the following tables:
- Table 1: WE documentation and analyses
- Table 2: WE Area design reviews
- Table 3: Specific WE reviews and analyses
- Table 4: Human Factor activities and analysis
- Table 5: WE Packages Follow-Up
- Table 6: Familiarisation of WE Design Basis



# Activity Plan (example) Specific analysis and reviews

- Coarse Chemical Health Risk Assessment (Coarse CHRA) of DECK and HULL
- Detailed Chemical HRA;
   CHEMICAL SAMPLING ARRANGEMENTS
- Detailed Chemical HRA;MEG & TEG SYSTEMS
- Detailed Chemical HRA; PIGGING OPERATIONS
- Detailed Chemical HRA;
   CHEMICAL INJECTION SYSTEMS

- WE Design Review; WIND AND WEATHER PROTECTION
- WE Design Review; ACCESS TO EQUIPMENT, VALVES AND INSTRUMENTS
- WE Design Review; ACCESS TO FLOODLIGHTS, LIGHT FIXTURES, F&G, TELECOM
- ERGONOMIC ANALYSIS OF MAJOR MANUAL WORK



### WE Package Follow-Up (example)

**BE: Bid Evaluation DR: Design Review** 

PI/SI: Package/Site Inspection Noise: Includes noise activity

- ER252 GAS COMPRESSORS(CENTRIFUGAL) High priority BE DR PI Noise
- •ER254 PROCESS & UTILITY PUMP Medium priority BE Noise
- •ER255 EMERGENCY & ESSENTIAL DIESEL GENERATOR High priority BE DR PI Noise
- •ER256 NITROGEN COMPRESSOR, AIR COMPRESSORS Medium priority BE Noise

